BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.L.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work:Improvements of drains and footpath in 4th phase 208 area in Attur ward No: 03 of Yelahanka New Town sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Rate	Rate in Words
1	*KSRB 2-1.1:Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled and after breaking of clouds and neatly dressed as per specification Specification No. KBS 2.1(a)/2.3.1* **(P-5 lt,2.1)**	**cum**	175.46	126.36	Rupees one hundred twenty six and paise thirty six only
2	Removing B.S Slab of Drain and stacking Page No. 28/ Item No. 5.32/ PWD SR 2013-14	Sqm	1102.86	50.11	Rupees fifty and paise eleven only
3	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 28/ Item No. 5.33/ PWD SR 2013-14	Sqm	1102.86	70.04	Rupees seventy and paise four only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete Page No. 28/ Item No. 5.31.1/ PWD SR 2013-14	Sqm	735.24	343.44	Rupees three hundred forty three and paise forty four only
5	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of nominal mix 1:2:4 using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification No. KBS 4.1,4.2, No.12/ Item No. 4.6/ PWD SR 2013-14	cum	16.71	4779.00	Rupees four thousand seven hundred seventy nine only
6	*Removing and resetting of kerb stones*	Mtr.	1114.00	49.68	Rupees forty nine and paise sixty eight only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Rate	Rate in Words
7	*KSRRB 15-19.1:Providing and applying ready mix priming coat over concrete/ masonry/asbestos cement sheet/ plastered surfaces including preparing the surface after thoroughly cleaning of oil grease, dirt and other foreign matter, and sand preparing including cost of materials, labour complete as per specifications.* ***(P-131, It.15.80)***	Sqm	501.30	23.76	Rupees twenty three and paise seventy six only
8	*KSRB 15-20.1:Providing and applying floor painting with ready mix paint in two coats (excluding primer coat) on new concrete/ asbestos cement sheet/plastered surfaces brushing to give an even shade after preparing the surface after througly cleaning oil dirt, dust other foreign matter and sand papering including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2* ***(P.131, It.15.83)***	Sqm	501.30	44.28	Rupees forty four and paise twenty eight only
9	*KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/kanker/moorum.Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter 1* ***(P-150, It.17.1)***	cum	175.46	94.82	Rupees ninety four and paise eighty two only
10	*Supplying and engaging tractor 50 Hp with driver and fuel with all accesaries to remove the silt and other works with all leads cost of labour complete as per specifications. PWD SR 2013-14 P XXXXVII, Sl.No 20)*	Day	156.00	2240.00	Rupees two thousand two hundred forty only
11	*Supplying and engaging Mazdoor hoavy ten nos per tractor per day with all accesaries to remove the silt and other works with all leads cost of labour complete as per specifications. (PWD SR 2013-14) (Pg.No:LV, Item No:05)*	Nos	780.00	191.81	Rupees one hundred ninety one and paise eighty one only
12	*Supplying and engaging JCB excavator crane with driver and fuel with all accesaries to remove the silt and other works with all leads cost of labour complete as per specifications. (Code no:1031, JCB Excavator) (Page No:XXXXVII, Item No:23)*	Day	37.00	6720.00	Rupees six thousand seven hundred twenty only

Signature of the Contractor

Assistant Executive Engineer
Byalerayanapura Sub-division
KRIDL BBMP, Bangalore

Executive Engineer,
Yelahanka Division,
BBMP, Bangalore